

**RESOLUTION 2010-17**

**A RESOLUTION OF THE CITY OF LAKE WALES, FLORIDA, REVISING RESOLUTION 2006-05 ADOPTING A TRANSITION PLAN FOR REMOVING OBSTACLES TO ACCESSIBILITY OF PUBLIC BUILDINGS.**

**WHEREAS**, the City of Lake Wales has determined that certain obstacles exist which prevent access to public buildings by handicapped individuals; and

**WHEREAS**, the City of Lake Wales is desirous of removing such obstacles; and

**WHEREAS**, it is necessary to budget sufficient financial resources and schedule remedial actions over a period of time to accomplish this goal; and

**WHEREAS**, a transition plan for budgeting sufficient financial resources and scheduling remedial actions was developed with the assistance of a committee consisting of handicapped individuals in the community appointed for this purpose; and

**WHEREAS**, Resolution 2003-03 adopted a Transition Plan for Removing Obstacles to Accessibility of Public Buildings; and

**WHEREAS**, Resolution 2006-05 adopted an updated Transition Plan for Removing Obstacles to Accessibility of Public Buildings; and

**WHEREAS**, many of the obstacles to accessibility have been removed in accordance with said Transition Plan; and


**WHEREAS**, removal of some accessibility obstacles that were scheduled for earlier fiscal years will be accomplished during FY10'11 and removal of remaining obstacles will be accomplished in FY12'13; and

**WHEREAS**, it is necessary to revise the City's Transition Plan for Removing Obstacles to Accessibility of Public Buildings to reflect the changes referenced above,

**NOW, THEREFORE, BE IT RESOLVED BY THE CITY COMMISSION OF THE CITY OF LAKE WALES, POLK COUNTY, FLORIDA** that the following is adopted:

1. Revised Transition Plan for Removing Obstacles to Accessibility of Public Buildings (Exhibit "A")

**THIS RESOLUTION INTRODUCED AND PASSED** by the City Commission of the City of Lake Wales, Florida at its regular meeting on August 17, 2010.

  
\_\_\_\_\_  
Mayor/Commissioner, City of Lake Wales

ATTEST:

  
\_\_\_\_\_  
City Clerk

**RESOLUTION 2010-17 EXHIBIT "A"**

**REVISED TRANSITION PLAN FOR REMOVING OBSTACLES  
TO ACCESSIBILITY OF PUBLIC BUILDINGS**

---

**CITY OF LAKE WALES, FLORIDA**

**EXHIBIT "A" - REVISED TRANSITION PLAN FOR REMOVING OBSTACLES TO ACCESSIBILITY OF PUBLIC BUILDINGS**

Priority: 1=High; 5=Low

1. Municipal Administration Building special conditions: none  
201 W. Central Avenue

Obstacles	Accessibility Method	Schedule	Committee Priority					Responsibility
			1	2	3	4	5	
Parking - slope of space and access aisle exceeds maximum (actual = 1.5:48)	Adjust slope to maximum 1:50	Budget in FY 12'13 to achieve compliance				x		Facilities Maint
Building entrance - exterior door closer exceeds maximum of 8.5 lbf	Adjust lbf to maximum of 8.5 or replace door closer	N/A - completed						

2. Fire Station special conditions: multi-story  
253 W. Central Avenue

Obstacles	Accessibility Method	Schedule	Committee Priority					Responsibility
			1	2	3	4	5	
None identified		N/A - no obstacles						

3. Old City Hall/JD Alexander Center - Polk State College special conditions: historic property, multi-story  
152 E. Central Avenue

Obstacles	Accessibility Method	Schedule	Committee Priority					Responsibility
			1	2	3	4	5	
Parking - spaces less than minimum 96" wide	Increase width of spaces to minimum width required	N/A - Ownership transferred to Polk State College. Corrections have been made according to Polk State College requirements.						
Parking - access aisle non-existent or less than minimum 60" wide	Provide access aisle at minimum width required							
Accessible Route - slope exceeds maximum 1:20	Adjust slope to maximum 1:20							
Accessible Route - exceeds .5" slope, needs ramp	Install ramp or adjust slope							
Ramps - not provided on accessible route with slope exceeding 1:20	Install ramp or adjust slope							
Ramp - tile is slippery when wet	Provide firm, stable, non-slip surface							
Ramp - handrails lack extension 1' beyond top and bottom of ramp	Provide extension or replace handrails to comply							

3. Old City Hall/JD Alexander Center - Polk State College  
152 E. Central Avenue

special conditions: historic property, multi-story

Obstacles	Accessibility Method	Schedule	Committee Priority					Responsibility
			1	2	3	4	5	
Building entrance - exterior door closer exceeds maximum of 8.5 lbf	Adjust lbf to maximum of 8.5 or replace door closer	N/A - Ownership transferred to Polk State College. Corrections have been made according to Polk State College requirements.						
Elevator - out of service	Restore service							
Toilets - not on accessible route	Provide accessible route							
Toilets - door closer exceeds 5 lbf maximum effort to open	Adjust lbf to maximum of 5 or replace door closer							
Toilets - unobstructed space not provided	Replace restrooms							
Warning Signals - no audible alarm	Install audible alarm							
Warning Signals - no visual, flashing exit signs	Install flashing exit signs							

4. Police Headquarters  
133 E. Tillman Avenue

special conditions: none

Obstacles	Accessibility Method	Schedule	Committee Priority					Responsibility
			1	2	3	4	5	
Parking - spaces not closest to accessible route	Move spaces	N/A - completed						
Parking - access aisle non-existent	Provide access aisle at minimum width required	N/A - completed						
Parking - spaces not marked with universal access code	Mark spaces as required	N/A - completed						
Building entrance - exterior door closer exceeds maximum of 8.5 lbf	Adjust lbf to maximum of 8.5 or replace door closer	N/A - completed						
Toilets - entrance door less than 32" wide or lacks lever handle or push/pull hardware	Install lever handles	N/A - completed						
Toilets - door closer exceeds 5 lbf maximum effort to open	Adjust lbf to maximum of 5	N/A - completed						

4. Police Headquarters (continued)  
133 E. Tillman Avenue

special conditions: none

Obstacles	Accessibility Method	Schedule	Committee Priority					Responsibility
			1	2	3	4	5	
Toilets - no grab bars at back of commode 33"-36" high, 1.25"-1.5" in diameter, and 1.5" clear of wall	Provide required grab bars	N/A - completed						
Toilets - toilet paper dispenser lower than 19" minimum above floor (actual=16")	Adjust position of dispenser	N/A - completed						
Toilets - mirror bottom higher than 40" maximum above floor (actual=57")	Adjust position of mirror	N/A - completed						
Toilets - towel dispenser and disposal unit higher than 40" maximum above floor in women's restroom (actual=57")	Adjust position of dispenser	N/A - completed						

5. Children's Museum  
323 S. Scenic Highway

special conditions: historic property

Obstacles	Accessibility Method	Schedule	Committee Priority					Responsibility
			1	2	3	4	5	
Parking - spaces not closest to accessible route	Move spaces	N/A - completed						
Parking - access aisle non-existent	Provide access aisle at minimum width required	N/A - completed						
Ramp - handrails lack extension 1' beyond top and bottom of ramp	Provide extension or replace handrails to comply	N/A - completed						
Ramp - no edge protection to prevent slipping off ramps	Provide edge protection	N/A - completed						
Ramp - requires level landing same width as ramp and minimum of 60" in length at top, bottom and turn of ramp	Provide level landings as required	N/A - completed						
Building entrance - exterior door exceeds maximum of 8.5 lbf	Adjust lbf to maximum of 8.5	N/A - completed						
Toilets - no accessible restrooms, can't access due to step-up and door widths	Requires construction of exterior restrooms, building cannot be modified sufficiently	N/A - completed						

5. Children's Museum (continued)  
323 S. Scenic Highway

special conditions: historic property

Obstacles	Accessibility Method	Schedule	Committee Priority					Responsibility
			1	2	3	4	5	
Drinking Fountains - no accessible drinking fountains	Provide accessible drinking fountain	Budget in FY 12'13 to achieve compliance			x			Recreation/Facilities
Warning Signals - no warning signals	Provide audible and visual warning signals	Budget in FY 12'13 to achieve compliance				x		Recreation/Facilities
Meeting Rooms - all rooms are not handicapped accessible	Install doorways of minimum width for accessibility if structure permits	N/A - completed						
Meeting Rooms - wheelchair locations access below minimum 48" long x 33" wide (forward) and 60" long x 33" wide (side)	?	N/A - completed						

6. SAL (Yellow) Depot  
324 S. Scenic Highway

special conditions: historic property

Obstacles	Accessibility Method	Schedule	Committee Priority					Responsibility
			1	2	3	4	5	
Parking - no designated handicapped parking spaces provided	Provide at least one space meeting all requirements for accessibility	Budget in FY 12'13 to achieve compliance			x			Recreation/Facilities
Accessible Route - slope exceeds maximum 1:20	Adjust slope to maximum 1:20	N/A - completed						
Ramp - not provided on part of accessible route with slope exceeding 1:20	Provide ramp with required handrails and edge protection	N/A - completed						
Toilets - entrance door less than 32" wide or lacks lever handle or push/pull hardware	Replace door to minimum width	N/A - completed						
Toilets - unobstructed space not provided	Reconstruct restroom to provide unobstructed space	N/A - completed						
Toilets - commode seat not required 17"-19" in height (currently 16.5")	Raise seat to required height	Budget in FY 10'11 to achieve compliance		x				Recreation/Facilities
Toilets - toilet paper dispenser lower than 19" minimum above floor (actual=16")	Adjust position of dispenser	N/A - completed						
Toilets - lavatory not required height with proper clearance	Raise lavatory to required height	N/A - completed						
Toilets - faucet handles not extended	Provide push type faucet or lever handles	Budget in FY 10'11 to achieve compliance			x			Recreation/Facilities

7. Depot Museum  
325 S. Scenic Highway

special conditions: historic property, multi-level

Obstacles	Accessibility Method	Schedule	Committee Priority					Responsibility
			1	2	3	4	5	
Parking - no access aisle	Provide access aisle at minimum 60" width required	N/A - completed						
Ramp - wooden handrails out of compliance with all codes	Provide extension or replace handrails to comply	N/A - completed						
Ramp - no edge protection to prevent slipping off ramps	Provide edge protection	N/A - completed						
Lift - operational only upon request	Provide signage indicating conditions of operation	N/A - completed						

8. Stuart House  
300 E. Central Avenue

special conditions: historic property

Obstacles	Accessibility Method	Schedule	Committee Priority					Responsibility
			1	2	3	4	5	
Parking - no designated handicapped parking spaces provided	Provide at least one space meeting all requirements for accessibility	Budget in FY 12'13 to achieve compliance			x			Recreation/Facilities
Accessible Route - slope exceeds maximum 1:20	Adjust slope to maximum 1:20	N/A - completed						
Ramp - handrails lack extension 1' beyond top and bottom of ramp	Provide extension or replace handrails to comply	Budget in FY 12'13 to achieve compliance			x			Recreation/Facilities
Building entrance - door width below minimum 32" requirement (actual=31")	Reconstruct entrance	Budget in FY 12'13 to achieve compliance				x		Recreation/Facilities
Toilets - no accessible restrooms due to door width and step-ups	Provide structural modifications necessary	Budget in FY 12'13 to achieve compliance				x		Recreation/Facilities

9. Crystal Lake Park Restrooms  
309 4th Street

special conditions: historic property

Obstacles	Accessibility Method	Schedule	Committee Priority					Responsibility
			1	2	3	4	5	
Parking - parking spaces are in sand	Provide hard surface for accessibility	Budget in FY 12'13 to achieve compliance	x					Recreation/Facilities

9. Crystal Lake Park Restrooms (continued) special conditions: historic property  
309 4th Street

Obstacles	Accessibility Method	Schedule	Committee Priority					Responsibility
			1	2	3	4	5	
Toilets - toilet paper dispenser lower than 19" minimum above floor (actual=16")	Adjust position of dispenser	N/A - completed						
Toilets - towel dispenser and disposal unit higher than 40" maximum above floor in women's restroom (actual=57")	Adjust position of dispenser	N/A - completed						

10. Tourist Club special conditions: historic property  
309 4th Street

Obstacles	Accessibility Method	Schedule	Committee Priority					Responsibility
			1	2	3	4	5	
Parking - no designated handicapped parking spaces provided	Provide at least one space meeting all requirements for accessibility	N/A - completed						
Accessible Route - sidewalk obstructed by brush and not in good repair	Clear brush and repair sidewalks	N/A - completed						
Accessible Route - requires 60" passing space at 200' intervals	Widen path to 60" at 200' intervals to allow passing	N/A - completed						
Building entrance - not on accessible route	Repair sidewalks	Budget in FY 12'13 to achieve compliance		x				Recreation/Facilities
Building entrance - entry not level and 7" step creates obstacle; requires maximum .5" height with leveled edge and maximum slope of 1:3	Install ramp	Budget in FY 12'13 to achieve compliance	x					Recreation/Facilities
Drinking fountains - no accessible drinking fountain	Provide at least one accessible drinking fountain	Budget in FY 12'13 to achieve compliance		x				Recreation/Facilities

11. Pram Fleet Building special conditions: storage only  
301 N. Lakeshore Blvd.

Obstacles	Accessibility Method	Schedule	Committee Priority					Responsibility
			1	2	3	4	5	
N/A		N/A - storage only						



12. Kiwanis Park Restrooms  
1000 N. Lakeshore Blvd.

special conditions: none

Obstacles	Accessibility Method	Schedule	Committee Priority					Responsibility
			1	2	3	4	5	
Parking - no designated handicapped parking spaces, not hard surfaced (needs curb cut)	Provide hard surface and at least one space meeting all requirements for accessibility	N/A - completed						
Accessible Route - no accessible route to entrance	Provide accessible route by installing sidewalk to ramp	N/A - completed						
Ramp - no edge protection to prevent slipping off ramps	Provide edge protection	N/A - completed						
Ramp - requires level landing same width as ramp and minimum of 60" in length at top, bottom and turn of ramp	Provide level landings as required	N/A - completed						
Toilets - toilet paper dispenser lower than 19" minimum above floor (actual=16")	Adjust position of dispenser	N/A - completed						
Toilets - mirror bottom higher than 40" maximum above floor (actual=57")	Adjust position of mirror	N/A - Mirror Removed due to vandalism.						
Drinking fountain - not on accessible route	Provide accessible route	N/A - completed						
Drinking fountain - spout should be 36" above floor (actual=35"); bottom of apron should be minimum 27" from floor (actual=26")	Adjust position of fountain	N/A - completed						

13. Lake Wales Public Library  
290 Cypress Gardens Lane

special conditions: multi-level

Obstacles	Accessibility Method	Schedule	Committee Priority					Responsibility
			1	2	3	4	5	
Parking (upper and lower) - no access aisle	Provide access aisle at 60" minimum width required	N/A - completed						
Parking (lower) - slope of space and access aisle exceeds maximum (actual = 1.5:48)	Adjust slope to maximum 1:50	Budget in FY 12'13 to achieve compliance	x					Library/Facilities
Parking (lower) - spaces not marked with universal access code	Mark spaces as required	N/A - completed						

13. Lake Wales Public Library (continued) special conditions: multi-level  
290 Cypress Gardens Lane

Obstacles	Accessibility Method	Schedule	Committee Priority					Responsibility
			1	2	3	4	5	
Toilets - unobstructed space not provided, too narrow for turn-around	Rebuild restrooms, enlarging space	N/A - completed						
Toilets - need grab bars at back and side of commode 33"-36" high, 1.25"-1.5" in diameter, and 1.5" clear of wall	Install grab bars	Budget in FY 12'13 to achieve compliance		x				Library/Facilities
Toilets - mirror bottom higher than 40" maximum above floor (actual=57")	Adjust position of mirror	Budget in FY 10'11 to achieve compliance			x			Library/Facilities
Toilets - towel dispenser and disposal unit higher than 40" maximum above floor in women's restroom (actual=57")	Adjust position of dispenser	Budget in FY 10'11 to achieve compliance			x			Library/Facilities
Toilets - faucet handles not extended	Provide push type faucet or lever handles	Budget in FY 10'11 to achieve compliance		x				Library/Facilities
Drinking fountain - spout should be 36" above floor (actual=35"); bottom of apron should be minimum 27" from floor (actual=26") DOWNSTAIRS	Adjust position of fountain	N/A - completed						
Drinking fountain - spout should be 36" above floor (actual=35"); bottom of apron should be minimum 27" from floor (actual=26") UPSTAIRS	Adjust position of fountain	Budget in FY 10'11 to achieve compliance			x			Library/Facilities

14. Vehicle Maintenance Building special conditions: not a public-access facility  
125 E. Crystal Avenue

Obstacles	Accessibility Method	Schedule	Committee Priority					Responsibility
			1	2	3	4	5	
Parking - no designated or accessible handicapped parking		N/A - not public access						
Accessible Route - no accessible route		N/A - not public access						
Building Entrance - no accessible entrance		N/A - not public access						
Toilets - no accessible restrooms		N/A - not public access						
Drinking Fountains - no accessible drinking fountain		N/A - not public access						

15. Water Division Office special conditions: not a public-access facility  
1021 Lake Wales Avenue

Obstacles	Accessibility Method	Schedule	Committee Priority					Responsibility
			1	2	3	4	5	
Parking - no designated or accessible handicapped parking		N/A - Destroyed by storm - City Storage, not public access						
Accessible Route - no accessible route								
Building Entrance - no accessible entrance								
Toilets - no accessible restrooms								
Drinking Fountains - no accessible drinking fountain								

16. Streets Barn special conditions: abandoned building  
129 W. Sessoms Avenue

Obstacles	Accessibility Method	Schedule	Committee Priority					Responsibility
			1	2	3	4	5	
N/A		N/A - abandoned						

17. Albert Kirkland Sr. Gymnasium special conditions: historic property  
409 3rd Avenue

Obstacles	Accessibility Method	Schedule	Committee Priority					Responsibility
			1	2	3	4	5	
Parking - no designated or accessible handicapped parking	Provide designated space	N/A - completed						
Toilets - door closer exceeds 5 lbf maximum effort to open (actual = 8-10 lbf)	Adjust lbf to maximum of 5 or replace closer	Budget in FY 10'11 to achieve compliance				x		Recreation/Facilities

18. Primary School Building/Boys & Girls Club special conditions: historic property undergoing renovation; not currently accessible to public  
Fourth Street

Obstacles	Accessibility Method	Schedule	Committee Priority					Responsibility
			1	2	3	4	5	
Remodeling to include compliance with accessibility requirements		N/A - completed						

19. CSX Building  
450 N. Scenic Highway

special conditions: historic property; not currently a public-access facility

Obstacles	Accessibility Method	Schedule	Committee Priority					Responsibility	
			1	2	3	4	5		
Parking - no designated or accessible handicapped parking	Remodeling for public access will include accessibility modifications	Budget in FY 10'11 to achieve compliance						x	Public Works / Facilities
Building Entrance - not on accessible route	Remodeling for public access will include accessibility modifications	Budget in FY 12'13 to achieve compliance						x	Public Works / Facilities
Toilets - entrance door less than 32" wide or lacks lever handle or push/pull hardware	Remodeling for public access will include accessibility modifications	N/A - completed							
Toilets - unobstructed space not provided	Remodeling for public access will include accessibility modifications	N/A - completed							
Toilets - need grab bars at back and side of commode 33"-36" high, 1.25"-1.5" in diameter, and 1.5" clear of wall	Remodeling for public access will include accessibility modifications	N/A - completed							
Toilets - commode seat not required 17"-19" in height	Remodeling for public access will include accessibility modifications	N/A - completed							
Toilets - urinal basin opening higher than 40" maximum above floor	Remodeling for public access will include accessibility modifications	N/A - completed							
Toilets - faucet handles not extended	Remodeling for public access will include accessibility modifications	N/A - completed							

20. Stuart Park Restrooms  
122 A Street

special conditions: CDBG funded; must be Section 504 compliant

Obstacles	Accessibility Method	Schedule	Committee Priority					Responsibility	
			1	2	3	4	5		
Parking - no designated or accessible handicapped parking	Provide at least one space meeting all requirements for accessibility	Budget in FY 10'11 to achieve compliance	x						Recreation/Facilities
Accessible route - surface texture not of firm, stable, non-slip material	Remove grass and sand, provide accessible route	N/A - completed							
Accessible route -slope exceeds .5", requires ramp	Add ramp or level 1" step	N/A - completed							
Building entrance - not on accessible route	Provide accessible route	N/A - completed							

21. B Street Community Services Center special conditions: CDBG funded; must be Section 504 compliant  
B Street

Obstacles	Accessibility Method	Schedule	Committee Priority					Responsibility
			1	2	3	4	5	
Parking - handicapped spaces not closest to building entrance	Move spaces closer to front of building	N/A - completed						

22. North Field Complex Restrooms special conditions: CDBG funded; must be Section 504 compliant  
Florida Avenue

Obstacles	Accessibility Method	Schedule	Committee Priority					Responsibility
			1	2	3	4	5	
Parking - access aisle needs re-striping	Re-stripe	Budget in FY 10'11 to achieve compliance	x					Recreation/Facilities
Accessible Route - slope to women's room exceeds .5"	Adjust slope or install ramp	Budget in FY 12'13 to achieve compliance	x					Recreation/Facilities
Ramp - need handrails minimum 30" to 34" high, extending 1' beyond top and bottom of ramp	Provide handrails that meet requirements for ramp rise exceeding 6" and run exceeding 72"	Budget in FY 10'11 to achieve compliance	x					Recreation/Facilities
Building entrance - women's room exceeds maximum .5" height and maximum slope of 1:2	Adjust height and slope, provide leveled edge	Budget in FY 12'13 to achieve compliance	x					Recreation/Facilities
Toilets - mirror bottom higher than 40" maximum above floor (actual=41-42.5")	Adjust position of mirror	N/A - completed						
Drinking fountain - box-type, not accessible (in kitchen)	Replace fountain in accessible location	N/A - completed						

23. James P. Austin Jr. Community Center special conditions: CDBG funded; must be Section 504 compliant  
315 N. Walker Street

Obstacles	Accessibility Method	Schedule	Committee Priority					Responsibility
			1	2	3	4	5	
Parking - no access aisle	Provide access aisle at minimum width required	N/A - completed						

23. Austin Community Center (continued)  
315 N. Walker Street

special conditions: CDBG funded; must be Section 504 compliant

Obstacles	Accessibility Method	Schedule	Committee Priority					Responsibility
			1	2	3	4	5	
Ramp - need handrails minimum 30" to 34" high, extending 1' beyond top and bottom of ramp	Provide handrails that meet requirements for ramp rise exceeding 6" and run exceeding 72"	Budget in FY 12'13 to achieve compliance	x					Recreation/Facilities
Ramp - no edge protection to prevent slipping off ramps	Provide edge protection	Budget in FY 12'13 to achieve compliance	x					Recreation/Facilities
Ramp - requires level landing same width as ramp and minimum of 60" in length at top, bottom and turn of ramp	Provide level landings as required	Budget in FY 12'13 to achieve compliance	x					Recreation/Facilities
Building entrance - exceeds maximum .5" height and maximum slope of 1:2	Adjust height and slope, provide leveled edge	Budget in FY 12'13 to achieve compliance	x					Recreation/Facilities
Toilets - need grab bars at back and side of commode 33"-36" high, 1.25"-1.5" in diameter, and 1.5" clear of wall FRONT	Correct 1" diameter grab bars to 1.25-1.5"	N/A - completed						
Toilets - towel dispenser and disposal unit higher than 40" maximum above floor FRONT	Adjust position of dispenser	N/A - completed						
Toilets - need grab bars at back and side of commode 33"-36" high, 1.25"-1.5" in diameter, and 1.5" clear of wall BACK	Correct 1" diameter grab bars to 1.25-1.5"	N/A - completed						
Toilets - towel dispenser and disposal unit higher than 40" maximum above floor BACK	Adjust position of dispenser	N/A - completed						

24. SPR Water Reclamation Plant  
840 Henry Street

special conditions: not a public-access facility, except for potential public use of meeting room

Obstacles	Accessibility Method	Schedule	Committee Priority					Responsibility
			1	2	3	4	5	
Parking - parallel to curb without adequate space between parked vehicles	Provide space with access area	Budget in FY 12'13 to achieve compliance				x		Public Works/Utilities
Accessible Route - no unobstructed path	Provide unobstructed path	Budget in FY 12'13 to achieve compliance				x		Public Works/Utilities
Curb ramps - 6.5" curb, ramp is needed	Provide curb ramps meeting accessibility requirements	Budget in FY 12'13 to achieve compliance			x			Public Works/Utilities

24. SPR Water Reclamation Plant (continued) special conditions: not a public-access facility  
840 Henry Street

Obstacles	Accessibility Method	Schedule	Committee Priority					Responsibility
			1	2	3	4	5	
Building entrance - not on accessible route	Provide curb ramps meeting accessibility requirements	N/A - completed						
Building entrance - exceeds maximum .5" height and maximum slope of 1:2	Adjust height and slope, provide leveled edge	N/A - completed						
Toilets - not accessible	Install fully accessible restrooms	N/A - completed						
Drinking fountain - not on accessible route	Install fully accessible restrooms	N/A - completed						

25. Cemetery Mausoleum special conditions: none  
1000 US Highway 27 S

Obstacles	Accessibility Method	Schedule	Committee Priority					Responsibility
			1	2	3	4	5	
Parking - no designated or accessible handicapped parking	Provide at least one space meeting all requirements for accessibility	N/A - completed						
Accessible Route - no accessible route	Install sidewalk	N/A - completed						

26. Cemetery Office special conditions: none  
1000 US Highway 27 S

Obstacles	Accessibility Method	Schedule	Committee Priority					Responsibility
			1	2	3	4	5	
Parking - no designated or accessible handicapped parking	Provide at least one space meeting all requirements for accessibility	Budget in FY 10'11 to achieve compliance		x				Cemetery/Facilities
Accessible Route - needs minimum head room of 80"	Modify structure to provide minimum head room	N/A - completed						
Accessible Route - slope exceeds .5", needs ramp (actual = 1")	Adjust slope or install ramp	N/A - completed						
Building entrance - needs level entry or sloped with a 32" door (actual = 30")	Modify structure to provide minimum door width	N/A - completed						
Building entrance - entryway not clear of obstacles (door jambs)	Modify structure to provide minimum door width	N/A - completed						
Building entrance - exceeds maximum .5" height and maximum slope of 1:2 (actual = 1" lip)	Adjust height and slope, provide leveled edge	N/A - completed						

26. Cemetery Office (continued) special conditions: none  
1000 US Highway 27 S

Obstacles	Accessibility Method	Schedule	Committee Priority					Responsibility
			1	2	3	4	5	
Toilets - not accessible	Install fully accessible restrooms	N/A - completed						

27. Willow Lawn Cemetery Restrooms special conditions: none  
4400 Washington Ave.

Obstacles	Accessibility Method	Schedule	Committee Priority					Responsibility
			1	2	3	4	5	
Two restrooms not accessible.	Combine 2 restrooms into single fully accessible restroom.	N/A - completed.						

27. Airport Hangars - Old "T" Hangars special conditions: none  
450 Airport Road

Obstacles	Accessibility Method	Schedule	Committee Priority					Responsibility
			1	2	3	4	5	
Accessible Route - no accessible route	Provide sidewalk	N/A - completed - Rebuilt Access Compliant						

28. Airport Hangars - New "T" Hangars special conditions: none  
450 Airport Road

Obstacles	Accessibility Method	Schedule	Committee Priority					Responsibility
			1	2	3	4	5	
No obstacles identified		N/A - no obstacles						

29. Airport FBO Facility special conditions: multi-level  
450 Airport Road

Obstacles	Accessibility Method	Schedule	Committee Priority					Responsibility
			1	2	3	4	5	
Parking - no access aisle	Provide access aisle at 60" minimum width required	N/A - completed - Rebuilt Access Compliant						
Building entrance - obstructed by sand	Provide hard surface to entrance							
Upper level - no access	Provide lift or elevator if public is admitted to upper level							